# **ORIGINAL**

# Antelope Lakes Sewer, LL



28N

2465 Shane Drive Prescott, AZE86505VED

Phone: (928) 717-2616 / Fax: 7162260 727-26210: 34

AZ CORP COMMISSION DOCKET CONTROL

February 19, 2008

Robin R. Mitchell Attorney, Legal Division Arizona Corporation Commission 1200 W. Washington St. Phoenix, AZ 85007-2927 Arizona Corporation Commission

DOCKETED

FEB 21 2008

DOCKETED BY
NR

RE:

Staff's **Third** Set of Data Requests to Antelope Lakes Sewer, LLC Docket #SW-20510A-07-0062

Dear Ms. Mitchell,

This letter is in response to the Staff's Third Set of Data Requests concerning Antelope Lakes Sewer, LLC.

MSJ 3-1

1. Question:

Confirm that for the proposed plant-in-service, the only effluent plant reported was the effluent lift station at an estimated cost of \$5,000.00.

Answer:

The effluent lift station estimated at \$5,000.00 is the correct amount for the lift station, however, the leach field was omitted. The Master Sewer Plan, included herewith as "Attachment 2", has been revised to show the leach lines. The leach lines with the proper engineering for percolation rates and sizing will be submitted to Arizona Department of Environmental Quality (ADEQ) as part of the Aquifer Protection Permit (APP).

2. Question:

If the above "A" is confirmed, the effluent system is not complete. In order to have a complete effluent system understanding, please provide:

- A. The effluent system method; i.e., recharge wells, leachfield, etc. Provide plans if available.
- B. The detailed cost estimate of the selected effluent system.
- C. Who will be responsible for funding of the effluent system.

Answer:

2(a)

The effluent disposal for the first two phases will be leach fields. Plans are to be submitted to ADEQ as part of the APP application. 2(B)

The cost estimate for the improvements have been revised to show the construction of the leach fields, and attached herewith as "Attachment 1".

2(C)

The funding for the leach fields will be included in the capital cost for the construction in the first phase of construction.

"Attachment 1" is the revised Antelope Lakes Sewer, LLC cost estimate

"Attachment 2" is the Master Sewer Plan for Antelope Lakes Sewer, LLC. Please note that the leach fields have been drawn into the plan to show the location where they will be engineered.

If you have any further questions please call Craig Garvin at (928)778-2600 or by email at <a href="mailto:craiggarvin@leviegroup.com">craiggarvin@leviegroup.com</a>.

/ 1 "

Craig W/ Garvin Chief Operating Officer

Antelope Lakes Sewer, LLC

CG:gma

Cc: N

Marlin Scott, Jr. Staff Assigned Docket Control Service List

# ANTELOPE LAKES SEWER COST ESTIMATE DECEMBER, 2007 (Revised 2/15/08)

#### PHASE I

217 Lots @ 193 gpd/lot = 41,881 gallons per day Treatment Plant Phase I = 45,000 gallons per day

#### **ESTIMATED COST** 400 L.F. 15" SDR-35 sewer @ \$45/L.F. \$ 18,000 600 L.F. 10" SDR-35 sewer @ \$38/L.F. \$ 22,000 7,700 L.F. 8" SDR-35 sewer @ \$26/L.F. \$ 200,200 217 - 4" Services @ \$300 ea. \$ 65,100 7 – 5' Dia. Manholes @ \$3,500 ea. \$ 24,500 22 – 4' Dia. Manholes @ \$3,000 ea. \$ 66,000 \$ 395,800 \$ 396,800 WASTE WATER TREATMENT PLANT 10,000 Gal. Equalization \$ 20,000 Flow Splitter 5,000 2-20,000 Gal. Aeration Tanks \$ 40,000 1 – 15' Dia. Clarifier \$ 17,500 Blowers \$ 22,000 \$ 15,000 Instrumentation Filtration System \$ 18,500 Disinfection \$ 18,450 \$ 20,000 Sludge Holding Headworks & Building - 15' X 25' \$ 25,000 Clarifier Building – 25' X 50' \$ 31,250 Equipment & Office Building – 30' X 38' \$ 85,500 Lift Station at Headworks \$ 42,500 Effluent Lift Station \$ 5,000 Leach Field & Force Main \$ 27,000 Yard Piping \$ 20,000 Grading & Excavation \$ 50,000 \$ 458,500 \$ 458,500 \$ 854,300 14% Engineering \$ 119,602 1% Permits & Fees 8,543 15% Contingency \$ 128,145

\$1,110,259

<sup>&</sup>quot;Attachment 1, Page 1 of 4"

#### PHASE II

249 Lots @ 193 gpd/lot = 48,057 gallons per day Treatment Plant Phase II = 45,000 gallons per day

#### **ESTIMATED COST**

900 L.F. 15" SDR-35 sewer @ \$45/L.F.	\$ 40,500
3,100 L.F. 12" SDR-35 sewer @ \$40/L.F.	\$ 124,000
4,100 L.F. 8" SDR-35 sewer @ \$26/L.F.	\$ 106,600
249 - 4" Services @ \$300 ea.	\$ 74,700
13 – 5' Dia. Manholes @ \$4,000 ea.	\$ 52,000
15 – 4' Dia. Manholes @ \$3,500 ea.	\$ 52,500
_	

\$ 450,300 \$ 450,300

#### WASTE WATER TREATMENT PLANT

Grading & Executation	=======================================
Grading & Excavation	\$ 25,000
Yard Piping	\$ 20,000
1 – 15' Dia. Clarifier	\$ 17,500
2 – 20,000 Gal. Aeration Tanks	\$ 40,000

<i>C</i> ,		
15% Contingency	\$	82,920
1% Permits & Fees	\$	5,528
14% Engineering	\$	77,392
	2	552,800
	•	

\$ 102,500

\$ 718,640

\$ 102,500

PHASE I - \$ 1,110,259 PHASE II - \$ 718,640 \$ 1,828,899

 $1,828,899 \div 466$  lots = 3,925/ lot

#### PHASE III

466 Lots from Phase I & II 677 Lots from Phase III 512 Lots from Phase III-A

1,655 Lots

# PHASE III

TRUNK LINE  2,650 L.F. 10" SDR-35 sewer @ \$38/L.F.  5,280 L.F. 8" SDR-35 sewer @ \$26/L.F.	\$ 100,700 \$ 137,280	
21 – 5' Dia. Manholes @ \$4,000 ea.	\$ 84,000	
	\$ 321,980	\$ 321,980
677 LOT SUBDIVISION	•	
24,040 L.F. 8" SDR-35 sewer @ \$26/L.F.	\$ 625,040	
677 - 4" Services @ \$300 ea.	\$ 203,100	
53 – 4' Dia. Manholes @ \$4,000 ea.	\$ 212,000	
	\$ 1,040,140	\$ 1,040,140
512 LOT SUBDIVISION		
23,700 L.F. 8" SDR-35 sewer @ \$26/L.F.	\$ 616,200	
512 - 4" Services @ \$300 ea.	\$ 153,600	
52 – 4' Dia. Manholes @ \$4,000 ea.	\$ 182,000	
	\$ 977,800	\$ 977,800
$$977,800 \div 512 \text{ lots} = $1,910/\text{lot}$		
WASTE WATER TREATMENT PLANT		
750,000 gpd		
3 Phases @ 250,000 gpd		
250,000 gpd @ \$4/gal	\$ 1,000,000	\$ 1,000,000
		\$ 3,339,920
	14% Engineering	\$ 467,588
	1% Permits & Fees	\$ 33,399
	15% Contingency	\$ 500,988 =======
		\$ 4,341,895
\$ 4,341,895 ÷ 1,655 = \$ 2,624/lot		
PHASE I - \$ 1,110,259		
PHASE II - \$ 718,640		
PHASE III - \$ 3,341,895		
\$ 5,170,884		

\$ 5,170,884 ÷ 1,655 lots = \$ 3,124/lot <u>PHASE IV</u>

## 1,470 Lots

## **SEWER & LATERALS**

1,470 Lots @ \$ 1,800/lot

\$ 2,664,000

# WASTE WATER TREATMENT PLANT

250,000 gal/day Expansion

\$ 1,000,000

\$ 3,664,000

\$3,664,000

14% Engineering 1% Permits & Fees \$ 512,960

\$ 36,640 15% Contingency \$ 549,600

\$4,763,200

 $4,763,200 \div 1,470 \text{ lots} = 3,240/\text{lot}$ 

PHASE I - \$1,110,259

PHASE II - \$ 718,640

PHASE III - \$3,341,895

PHASE IV - \$4,763,200

 $$9,933,994 \div 3,125 \text{ lots} = $3,179/\text{lot}$ 

#### PHASE V

Balance of treatment plant as required.

